VIBE 6030

60" x 30" x 19"

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



MODEL	тми	TUB
Drop-in Standard 1 1/2" deck	BVIBRD00T-XX	BVIBRD00N-XX
Alcove – Left Standard 1 1/2" deck	BVIBRB0LT-XX	BVIBRB0LN-XX
Alcove – Right Standard 1 1/2" deck	BVIBRBORT-XX	BVIBRBORN-XX
Slim deck	BVIBRD10T-XX	BVIBRD10N-XX
Slim deck – Left	BVIBRB1LT-XX	BVIBRB1LN-XX
Slim deck – Right	BVIBRB1RT-XX	BVIBRB1RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$
Geysair®	Included
Illuzio Chromatherapy BCHRO6	\$

TUB Soaker	\$
Illuzio Chromatherapy BCHRO6	\$
WarmTouchShell® BWTS	\$
DOT control	Included with therapy

FEATURES				
Installation type		Drop-in, Undermount & Alcove (3 walls)		
No. of bathers	•	Imp. gallo	ns	36
US gallons	44	Integrated tile flange Include		Included
INTEGRATED WASTE & OVERFLOW BOVERINI-XX				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10		Installed & Included		
STANDARD COLOR				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH		
UltraVelour Matte Finish (White only) BVEL	\$	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX		
Matte Black 19, Satin Brass 18	\$	
SKIRT MULTIFIT (standard 11/2" deck only) BSMUL-XX		
White 01, Biscuit 02	\$	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$	
Brass waste kit BDRCB	\$	

Don't forget that an integrated tile flange is available at no extra cost.

You must specify drain position (right or left).

Turbine must be remotely installed in certain conditions.

With the control on the deck, a complete shower door cannot be installed. Don't forget to specify the finish of the integrated waste & overflow.


TOTAL PRICE






VIBE 6030

INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Outside edge to center of overflow	2 1/2"
С	Total length	60"
D	Total width	30"
E	Bathing well length	44"
F	Bathing well width	19 1/8"
G	Deck width	1 7/8"
Н	Deck width at drain end	2"
ı	Height from bottom of bath to top deck	18 1/2"
J	Height from drain to center of overflow	14 1/2"
K	Slope of backrest	27°
L	Height from bottom of deck to top std deck	1 1/2"
М	Height from bottom of deck to top slim deck	1/2"
N	Tile flange height	1"

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	Should be 70% of water capacity of TUB or greater.	
Turbine	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 hz , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 hz , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The GEYSAIR must always be accessible and connected to the hot water supply (provide access) Turbine must be remotely installed in certain conditions. Integrated tile flange is included (specify right or left).	
	Integrated tile flange is included (specify right or left). t be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/documentation/documentation).	

Cutting template	# 90000078
Approx. shipping weight	200 lbs
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $[\]hbox{* Some restrictions apply} \mid \hbox{www.bainultra.com/warranty}$





The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.